

Facility Management Division

Prime/HO/FMD/2022/ Bashabo Br

February 23, 2022

Sub: Request for submission of proposal for Minor renovation of Bashabo Branch, Dhaka.

Dear Sir,

Please know that Prime Bank Limited intends to **Minor renovation of Bashabo Branch, Dhaka**. For this purpose, we are inviting you to submit financial offer along with technical specification of your work in your letterhead pad using following format:

Terms & Conditions:

1. Eligibility and other conditions:

- A. Practical work experience of minimum 05 (Five) years.
- B. Should have valid Registration, Ownership Document, VAT & BIN Certificate, up to date Trade License, Bank solvency certificate along with 6-month bank statement.
- C. Practical work experience to execute such type of work for minimum amount of Taka 20 Lac or above in a single work order.
- D. Vendor with any kind of dissatisfaction work experience with Prime Bank Ltd, will be disqualified. Their financial proposal will not be acceptable.

2. Payment: Payment will be made within 30 (Thirty) days from receipt of bill from the supplier. Payment will be made as per the following terms and conditions:


- A. 90% of the unit price will be paid after satisfactory installation of the equipment & subsequent certification of concerned division/concerned users.
- B. Remaining 10% of total price will be paid to the supplier after 06 (Six) months of satisfactory operation of the equipment.
- C. Bank will deduct VAT & AIT as per govt. rules.

3. Please submit your proposal in your company's letterhead pad as per above mentioned format duly signed by your company's authorized representative in the **tender box kept at FMD, Facilities Tower (6th Floor), Kha-199/2, Maddhya Badda, Pragati Sarani, Dhaka-1212 on or before 03 March 2022 (02:00 pm) and clearly marked "Minor renovation of Bashabo Branch, Dhaka" on the top of the envelope. No quotations shall be dropped before or after this time period.**

4. PBL reserves the right to accept or reject any quotation without any explanation.

5. For any BOQ related query please contact with Mr. Delwar Hoosain Saidy- **01701204025**

Thanking you.



SAVP & Head

Facility Management Division

Prime Bank Limited, Head Office-Adamjee Court Annex Building-2 (3rd Floor), 119-120, Motijheel C/A, Dhaka-1000.

RFQ FOR MINOR REPAIR & RENOVATION WORKS OF BASABOO BRANCH, DHAKA

SL	PARTICULARS	UNIT	QTY	RATE TK	AMOUNT TK
A	CIVIL WORK				
1	Dismanling work- ceiling, plaster and tiles etc	L/S	1		
2	Plaster work	sft	42		
3	Tiles work (24"x24" Mirror Polish-nearly similar with existing color, Brand: RAK)	sft	80		
4	Staircase Step Tiles replace work (10"x12" Homogeneous -nearly similar with existing color, Brand: RAK)	sft	60		
5	Existing Texture Paint remove and repaint	sft	210		
6	Fabrics Desk Deep Clean	sft	120		
7	Granite Change -similar with existing color & grade.	sft	16		
B	PAINT WORK				
8	Plastic Paint-03 coats, Brilliant white-Berger/Asian Paint	sft	6900		
9	Enamel Paint	sft	220		
10	Wooden Polish work	sft	400		
C	PARTITION & PANELLING WORK				
11	DROP PARTITION (3" thick) Supply, fitting & fixing drop partition made of 12 mm gypsum / Plain Partex board fixed over frame work of 2" X 1" best quality seasoned Garjon wood (with bituminus coated) section at a hieght from RCC roof slab to top of glass door and 3 coats of plastic paint over primer coat, putty, racking out joints etc.	rft	18		
12	PANELLING ON WALL Supply, fitting & fixing wall cladding made of 2"x1" garjon frame @ 2'x2' grid line, frame over pasted 12mm thick plain partex, plain partex over pasted 3mm thick decorative/ engineering ply with mat vernish including.	sft	180		
13	Wall panelling with 1mm HPL pasting (Cheque Writing desk wall)	sft	120		
14	Cheque Writing Desk (5'-0" x0'-10"x0'-8")	job	2		
15	Damped wall PVC Board pasting with plastic paint	sft	580		
16	DECORATIVE WALL PANELING WITH WAVE BOARD Supplying, fitting & fixing wall paneling ½" thick with plaine partex board over Decorative 3D wave board paste, main structure Gargaon Wood frame all complete as per design, drawing and As per approval of authority.all complete as per design, drawing and and directions of the consulting architect and full satisfaction of the Consultant.	sft	140		
17	10MM FRAMELESS BACK PASTED GLASS PANELING / PARTITION Supply, fitting & fixing fixed frameless NON TEMPERED Back Stiker-logo water print pasted glass Planeling / partition made of 10mm thick clear float glass fixed on top and bottom with silver colour best quality ss knob with accessories like sealant, neoprene, other hardware etc. having DIAMOND CUT bevelled edge at all exposed edges, (same as Uttara/Elephant Road Branch)	sft	78		
D	DOOR & DOOR FITTING				
18	Glass Door Closer (Supply & fitting, VVP-category A)	set	3		
19	Glass Door Lock (supply & fitting)	set	4		
20	Glass Door U shape Handle (supply & fitting)	set	1		
21	Logo with Letter (same as Cash Section Back wall of Elephant Road Branch) (supply & fitting)	pcs	1		
E	CEILING WORK				



22	Mineral Board Ceiling (Supply with fitting of mineral board (24"x24") including new frame cross-T, main-T.	sft	1900		
23	Replacement & refitting with necessary Cross & Main T	sft	560		
24	PVC Board ceiling (Including Cross T Main T , 24"x24"	sft	262		
25	SOLID CEILING Supplying fitting & fixing of plain gypsum fired board ceiling with imported (Brand: Elephant or equivalent) 12mm thick gypsum board size : 8'x 4', MS thread Rod, omega chanel frame suspended from roof .	sft	160		
F	CABINET & TABLE WORKS				
26	Low Height Cabinet repair with necessary fitting	sft	24		
27	Over Head Cabinet (10'x2') (new supply & fitting)	sft	20		
28	Table Top Change (1" Melamine Board Anatol Color)	sft	45		
29	Bench Type Table with Leg support (17' x 1'-5" x 2'-6")	sft	25		
30	Cabinet Handle replace	pcs	16		
31	Cabinet Hardware Change/Kobja	pcs	14		
32	Cabinet Lock Change	pcs	15		
33	Mobile Drawer Handle with Central Lock Change	pcs	12		
34	Low /Full Height Cabinet back ply change with leg support repair	sft	364		
35	Mobile Drawer Repair with lock change	pcs	12		
G	ELECTRIC CABLING & LIGHTING WORK				
36	24" x 24" LED PANEL LIGHT (Energyplus)	pcs	34		
37	6"x6" LED Panel (Energyplus)	pcs	20		
38	Spot Light 360 degree movable (Energy plus)	pcs	27		
39	T5 Tube Light (China)	pcs	16		
40	1C- 1.5rm BYA BRB Cable	coil	1.5		
41	Proper Cabling work: Service desks/Officials desk/Head of Branch Chamber CCTV DVR Cables, Power & LAN cables need to cover by 1"/1 1/2" flexible pipe	job	1		
42	False Cover	pcs	6		
43	Multi Socket	pcs	6		
44	1 Way 2 Gang Switch	pcs	1		
45	Face Plate Modular with MK Box	pcs	3		
46	Exhaust Fan 8-12"	pcs	1		
H	FLOOR CLEAN/INTERNAL STAIR, WOODEN CEILING & COLUMN PANELING CLEAN & POLISH WORK				
47	Floor Tiles Acid Clean & Repointing	sft	2500		
48	Toilet floor Acid Clean & Repointing	sft	270		
49	Internal Stair/Duplex Stair Marble clean & Polish work	sft	248		
I	CURTAIN/ BLINDS				
50	Rollar Blinds	sft	270		
51	Vertical Blinds (for Pantry)	sft	90		
K	SANITARY WARE & FITTING				
52	Commode Change RAK Orient (White)	pcs	1		
53	Commode/PAN Acid Clean with Ploish	pcs	5		
54	Basin Acid Clean with Ploish	pcs	6		
55	Toilet zone wall tiles acid clean (5 toilets)	job	1		
56	Magic Pipe/Hush Pipe	pcs	5		
57	Hand Push-Sattar/Nazma/Sharif	pcs	4		
58	Bipcock-Sattar/Nazma/Sharif	Pcs	5		
59	PVC Floor Mat (5mm thick)	sft	80		
60	Special Mirror with required ss Knob (For 4 toilets)	sft	37		
Total Amount TK					

