

Facility Management Division

Prime/HO/FMD/2022/ IBB Dilkusha Br

February 23, 2022

Sub: Request for submission of proposal for Minor renovation of IBB Dilkusha, Dhaka.

Dear Sir,

Please know that Prime Bank Limited intends to **Minor renovation of IBB Dilkusha, Dhaka**. For this purpose, we are inviting you to submit financial offer along with technical specification of your work in your letterhead pad using following format:

Terms & Conditions:

1. Eligibility and other conditions:

- A. Practical work experience of minimum 05 (Five) years.
- B. Should have valid Registration, Ownership Document, VAT & BIN Certificate, up to date Trade License, Bank solvency certificate along with 6-month bank statement.
- C. Practical work experience to execute such type of work for minimum amount of Taka 20 Lac or above in a single work order.
- D. Vendor with any kind of dissatisfaction work experience with Prime Bank Ltd, will be disqualified. Their financial proposal will not be acceptable.

2. Payment: Payment will be made within 30 (Thirty) days from receipt of bill from the supplier. Payment will be made as per the following terms and conditions:

- A. 90% of the unit price will be paid after satisfactory installation of the equipment & subsequent certification of concerned division/concerned users.
- B. Remaining 10% of total price will be paid to the supplier after 06 (Six) months of satisfactory operation of the equipment.
- C. Bank will deduct VAT & AIT as per govt. rules.

3. Please submit your proposal in your company's letterhead pad as per above mentioned format duly signed by your company's authorized representative in the **tender box kept at FMD, Facilities Tower (6th Floor), Kha-199/2, Maddhya Badda, Pragati Sarani, Dhaka-1212 on or before 03 March 2022 (02:00 pm) and clearly marked "Minor renovation of IBB Dilkusha, Dhaka" on the top of the envelope. No quotations shall be dropped before or after this time period.**

4. PBL reserves the right to accept or reject any quotation without any explanation.

5. For any BOQ related query please contact with Mr. Delwar Hoosain Saidy- **01701204025**

Thanking you,



SAVP & Head

Facility Management Division



RFQ FOR MINOR REPAIR & RENOVATION WORKS OF IBB DILKUSHA, DHAKA

SL	PARTICULARS	UNIT	QTY	RATE TK	AMOUNT TK
A	CIVIL WORK				
1	Dismantling work-Ceiling	L/S	1		
2	Plaster work	sft	10		
B	PAINT WORK				
3	Plastic Paint	sft	1900		
4	Enamel Paint	sft	220		
5	Wooden Polish work	sft	120		
C	PARTITION & PANELLING WORK				
6	DROP PARTITION (3" thick) Supply, fitting & fixing drop partition made of 12 mm gypsum / Plain Partex board fixed over frame work of 2" X 1" best quality seasoned Garjon wood (with bituminus coated) section at a hieght from RCC roof slab to top of glass door and 3 coats	rft	20		
7	3" FULL HEIGHT PARTITION Supplying, fitting & fixing full height partition made by double faced ½ thick plain PARTEX board on 2" x 2" section seasoned Garjan wood framing, with nails & glue,in/c making horizontal / vertical grooves, fixing the same on floors/walls by electric drill machine & mending good the damage if any during execution of the work in/c cost of all materials, accessories, scaffoldings, labour for installation, screws, nails etc, in/c paint atleast 3 coats over a coat of priming in/c necessary sanding, putty works etc.	sft	50		
8	HPL SHEET [Brand: MARINOLAM, INDIA OR Equivalent] Supplying, fitting & fixing High Pressured Decorative Laminates (1mm thick) sheets upon partitions with glue, making the surface absolutely smooth and bubble free(Same as Uttara/Elephant Road Branch)	sft	80		
9	PANELLING ON WALL Supply, fitting & fixing wall cladding made of 2"x1" garjon frame @ 2'x2' grid line, frame over pasted 12mm thick plain partex, plain partex over pasted 3mm thick decorative/ engineering ply with mat vernish including.	sft	220		
10	Cheque Writing Desk same as Elephant Road Branch	job	2		
11	DECORATIVE WALL PANELING WITH WAVE BOARD Supplying, fitting & fixing wall paneling ½" thick with plaine partex board over Decorative 3D wave board paste, main structure Gargaon Wood frame all complete as per design, drawing and As per approval of authority.all complete as per design, drawing and and directions of the consulting architect and full satisfaction of the Consultant.	sft	100		
12	10MM FRAMELESS BACK PASTED GLASS PANELING / PARTITION Supply, fitting & fixing fixed frameless NON TEMPERED Back Stiker-logo water print pasted glass Paneling / partition made of 10mm thick clear float glass fixed on top and bottom with silver colour best quality ss knob with accessories like sealant, neoprene, other hardware, ss knob and Alluminum U Channel -etc. having DIAMOND CUT bevelled edge at all exposed edges, (same as Uttara/Elephant Road Branch)	sft	251		
	Frosted Paper	sft	140		
D	DOOR & DOOR FITTING				



13	ALUMINUM FRAME SLIDING (at toilet entrance lobby)	sft	140		
14	Glass Door Closer (Supply & fitting, VVP-category A)	set	2		
15	Logo with Letter (same as Cash Section Back wall of Elephant Road Branch) (supply & fitting)	pcs	1		
E	CEILING WORK				
16	Mineral Board Ceiling (Supply with fitting of Mineral board ceiling (24"x24"))	sft	1750		
17	PLAIN GYPSUM CEILING/SOLID CEILING Supplying fitting & fixing of plain gypsum fired board ceiling with imported (Brand: Elephant or equivalent) 12mm thick gypsum board size : 8'x 4', MS thread Rod, omega chanel frame suspended from roof .	sft	80		
F	CABINET & TABLE WORKS				
18	Low Height Cabinet	sft	24		
19	Over Head Cabinet (13'x2')	sft	26		
20	Table Top Change (1" Melamine Board Anatol)	sft	45		
21	Cabinet Hardware Change/Kobja	pcs	10		
22	Cabinet Lock Change	pcs	14		
23	Mobile Drawer Handle Change	pcs	12		
24	Mobile Drawer Central Lock Change	pcs	6		
25	Low /Full Height Cabinet back ply change with leg support repair	sft	200		
26	Mobile Drawer Repair	pcs	6		
G	ELECTRIC CABLING & LIGHTING WORK				
27	24" x 24" LED PANEL LIGHT (Energyplus)	pcs	26		
28	6"x6" LED Panel (Energyplus)	pcs	12		
29	Spot Light 360 degree movable (Energy plus)	pcs	12		
30	T5 Tube Light (Transtec/Superstar)	pcs	14		
31	1C- 1.5rm BYA BRB Cable	coil	1.5		
32	Proper Cabling work: Service desks/Officials desk/Head of Branch Chamber CCTV DVR Cables, Power & LAN cables need to cover by 1"/1 1/2" flexible pipe	job	1		
33	False Cover	pcs	6		
34	Multi Socket	pcs	4		
35	1 Way 4 Gang Switch	pcs	2		
36	1 Way 3 Gang Switch	pcs	2		
37	1 Way 2 Gang Switch	pcs	1		
38	Face Plate Modular with MK Box	pcs	5		
39	Bell Push	pcs	2		
	FLOOR CLEAN/INTERNAL STAIR, WOODEN CEILING & COLUMN				
H	PANELING CLEAN & POLISH WORK				
40	Floor Tiles Acid Clean & Repointing	sft	1700		
41	Toilet floor Acid Clean & Repointing	sft	150		
I	CURTAIN/ BLINDS				
42	Rollar Blinds	sft	120		
43	Vertical Blinds	sft	30		
K	SANITARY WARE & FITTING				
44	Commode Acid Clean with Ploish	pcs	4		
45	Basin Acid Clean with Ploish	pcs	2		
49	PVC Floor Mat (5mm thick)	sft	80		
50	Special Mirror with required ss knob	sft	18		
Total AMOUNT TK					

