

Facility Management Division

Request For Quotation (RFQ) for Construction & Interior Decoration of ATM (CRM) Booth at KDS Textile Mills Limited, Mohra, Chandgaon, Chattogram


Sealed tenders are hereby invited by Prime Bank PLC. from reputed and eligible Interior Decoration Contractor(s)/Architectural and/or Engineering Firms for Construction & Interior Decoration Work of STM (CRM) Booth as per following Schedule:

SN	Name of Project as per Tender Document	Pre-bid Meeting Schedule		Date of Submission
		Date	Time	
1	Construction & Interior Decoration of ATM (CRM) Booth at KDS Textile Mills Limited, Mohra, Chandgaon, Chattogram	25 June 2024	03.00 pm-3.30 pm	27 June 2024

Eligibility and other conditions:

Interested bidders may collect BOQ document for the said work on submission of a request letter addressing the undersigned as well as documentary evidence of the followings:

- Should have work experience of minimum 05 (Five) years in interior decoration and furniture work of Bank's Branch and/or Head Office, Commercial Space for Local/Multinational Group of Companies. Copy of oldest Trade License need to be provided as proof.
- Should have work experience to execute relevant type of work for minimum amount of Taka 15 Lac or above in a single work order in last 2 (two) years. Please submit proof of documents with work completion certificate.
- Provide valid Trade License/Incorporation Certificate/Ownership Document, BIN, TIN Certificate & Bank Solvency Certificate.
- The Following Technical Personnel of the firm should meet below criteria:
 - Civil Engineer (Permanent/Contractual):** Having working experience for a minimum period of 05 years in relevant field (Bachelor of Science/Diploma). Please submit proof of documents.
 - Electrical Engineer (Permanent/Contractual):** Having working experience for a minimum period of 05 years in relevant field (with Bachelor of Science/Diploma). Please submit proof of documents.
- Vendor with previous bad record with Prime Bank PLC. will be directly disqualified. Their financial offer will not be acceptable and will not be opened.
- Any Fake, Tempering of Data, Manipulation or any kind of unusual approach or failure to submit the proposal/offer within the stipulated time frame will be treated as "Disqualification" to attend to the bidding.
- The interested bidders shall have to attend a pre-bid meeting at the office of the undersigned at 03:00 pm on 25.06.2024. (Physical Meeting) Venue: Prime Tower (10th Floor), Plot # 8 & 35, Nikunjo-2, Khilkhet, Airport Road, Dhaka-1219.
- Each tender must be submitted in sealed envelope mentioning the name of work on top of the envelope to the office of the undersigned as per aforesaid date on 27.06.2024 within 3:00 pm.
- The BOQ must be submitted in 2(two) envelope system i.e. one "Technical Proposal" and another "Financial Proposal" mentioning Technical/Financial proposal on the top of each envelope. These two proposals will be submitted together in a sealed envelope. All the envelopes will contain the full name and address of the participant company. The name, address and telephone number of the contact person should be mentioned in the forwarding letter both of the "Technical Offer" and the "Financial Offer".
- Point of Contact: Md. Imran Shekh, Cell: 01701204033
- Banks Right: Banks reserves the right to accept/ cancel/ reject any or all offers without assigning any reason. Banks is not obliged to purchase the lowest offer or any offer at all. Banks (PBL) reserves the right to share the Bidder's response to this RFQ with its advisors and Purchaser Business Units. Banks reserves the right to: conduct negotiations with one or more Bidder and/ or accept the Bid without any negotiations.
- Please drop your tender - Prime Tower (Ground Floor), Plot 8 & 35 Airport Road, Nikunja-2, Dhaka -1229.
- Interested bidders are requested to collect BOQ hard copy from PBPLC, Prime Tower (10th Floor), Plot 8 & 35 Airport Road, Nikunja-2, Dhaka -1229.


 Unit Head of Procurement
 Facility Management Division
 Tel: 09610990000-Ext. 11012

Financial Proposal for KDS ATM, Chittagong		
Sl.	Item	Amount
1	Structure	
2	Interior	
	Grand Total=	

In Word:

Note: All unit price must be included VAT, AIT & all other charges.



KDS off-site ATM Booth-Structure

Sl.	Description	Unit	Quantity	Rate (in Tk.)	Amount (in Tk.)
Civil Work					
1	Earth excavation	cft	576		
2	Land development by sand & coarse aggregate, Ratio: 2:3.	cft	72		
3	Sand Filling	sft	432		
4	Brick soling	sft	240		
5	20" Brick wall	cft	120		
6	15" Brick wall	cft	90		
7	10" Brick wall	cft	72		
8	10" Brick wall - Stair Step	cft	56		
9	5" Brick wall	sft	480		
10	Plaster work	sft	1,104		
11	RCC Work (Column) including shutter work	cft	44		
12	RCC Work (Grade Beam) including shutter work	cft	33		
13	RCC Work (6" Slab-Rooftop) including shutter work	cft	48		
14	RCC Work (4" Floor) including shutter work	cft	32		
15	EARTH CONTINUITY CONDUCTOR Supply and installation of PVC insulated cable (single core, BRB cable) used as earth continuity conductor along with cables, in pre installed conduit, including connection to various metallic parts of following sizes etc. all complete as per full satisfaction of Engineer in charge. Min120ft & resistance must be less than 1 ohm.	nos	1		
Total Tk.					



KDS off-site ATM Booth-Interior & Exterior

Sl.	Description	Unit	Quantity	Rate (in Tk.)	Amount (in Tk.)
A. Tiles Works					
1	Stair Tiles	sft	64		
2	24"x24" Homogenous Mirror Polish tiles	sft	120		
B. Partition & Panelling Work					
1	GLASS PARTITION (with U-Channel) FIXED Supply, fitting & fixing fixed glass partition made of 10 mm thick clear 'Nasir' glass fixed with protector bit & others accessories. all complete as per direction and full satisfaction of the Engineer in charge	sft	48		
2	10mm Tempered Single Swing Glass Door including closer, lock & handle	nos	1		
3	PVC Board Pasting 5mm	Sft	320		
4	Mid Partition including door	sft	64		
C. Ceiling Work					
1	MINERAL BOARD CEILING Supply, fitting and fixing of Mineral board false ceiling of approved quality in working area over powder coated T-bar of section 1" X 1.5" and L-angle of section 1" X 1" at edges, at 2'-0" X 2'-0" grid suspended ceiling by rowel plug, iron angles, 12 SWG G.I. wire, screws, hooks, nails etc. maintaining straight lines and desired finished level at bottom face with vertical or beams by electric drill machine and mending damage if any during the materials, accessories, scaffolding, labour for installation etc. all complete as per design, direction and full satisfaction of the Engineer in charge.	sft	96		
2	Decorative Ceiling & Louver Partition	sft	72		
D. Electrical Work (Same as Dagonbhuiyan Branch or equivalent)					
1	PIPE WORK				
i)	3/4" dia PVC	rft	130		
ii)	3/4" dia flexible	rft	50		
2	CABLE WORK				
A.	Supply & installation including termination of PVC insulated or PVC sheathed single core BRB cable including all accessories of the following sizes etc. all complete as per full satisfaction of Engineer in charge.				
i)	2.5rm	coil	2		
ii)	2.50rm re	coil	1		
iii)	1.5 rm	coil	2		
iv)	4 rm	coil	1		
v)	1x10 rm , BYA (BRB)	rft	400		
3	SDB Box (Energypac)	set	1		
4	40A DP MCB (legrand India)	pcs	1		
5	20A SP MCB (Legrand India)	pcs	2		
6	16A SP MCB	pcs	3		
7	10A SP MCB	pcs	1		
8	6"x6" Panel Light, Energypac	set	12		
9	LED Surch light set (20 watt)	set	3		
10	Supply and fixing of 3"X3" steel box(MK Type) made of 18SWG sheet hammer painted etc. all complete up to testing & commissioning as per full satisfaction of Engineer in charge.	nos	12		
11	Supply and installation of following switch and socket of approved quality. (MK Singapore)				
12	5A, 3 Gang (1 way) switch(LEGRAND,Energypac)	pcs	5		
13	5A, 4 Gang (1 way) switch(LEGRAND)	pcs	2		
14	15 A, 3 pin combaind socket	pcs	4		
15	3 pin socket flat pin(15AMP) Energypac	pcs	2		
16	Cable wiring & AC Water Line groping	LS	1		



E. Miscellaneous Work					
1	PLASTIC PAINT (Berger : Color Bank) Painting work in 3 coats of plastic paint of approved colour and quality over a coat of primer seal including cleaning the surface, rubbing by pumice stone, sand papering, synthetic putty and necessary scaffolding for all floors etc. all complete as per design, direction and full satisfaction of the Engineer in charge. (Apple White:White=1:4)	sft	600		
2	ENAMEL PAINT (Berger : Color Bank) Painting work in 3 coats of plastic paint of approved colour and quality over a coat of primer seal including cleaning the surface, rubbing by pumice stone, sand papering, synthetic putty and necessary scaffolding for all floors etc. all complete as per design, direction and full satisfaction of the Engineer in charge. (Apple White:White=1:4)	sft	130		
4	ALUMINIUM COMPOSITE PANEL Supply, fitting & fixing of aluminium composite panel (Made in Japan-Mitsubishi/Germany-Aluco Bond brand) of approved color and quality cladded on standard and necessary aluminium or galvanized framing etc. all complete as per design, direction and full satisfaction of the Architect / Engineer.	sft	480		
5	GUARD TOOL Supply, fitting & fixing of locally available best quality guard tool including necessary hardware & accessories etc. all complete as per design, direction and full satisfaction of the Engineer in charge	each	1		
6	Wastage Paper Basket (RFL)	each	1		
7	PVC FLOOR MAT	sft	8		
8	SS Canopy	sft	35		
9	Rolling Shutter	sft	120		
11	IT Networking	Node	2		
				Total Tk.	

