

Sub : RFQ for shifting Internal Audit Department from 2nd, 6th & 7th floor of Alhaj Tower to 2nd Floor of Facilities Tower, Middle Badda, Dhaka.

Dear Sir,

Reference may please be made on the above mentioned subject.

We would like to inform you that we are inviting tender for shifting Internal Audit Department from 2nd, 6th & 7th floor of Alhaj Tower to 2nd Floor of Facilities Tower, Middle Badda, Dhaka.

You may participate in the tender procedure by submitting Financial Proposal in sealed envelope for the captioned work. If you are interested, you may visit to above mentioned places for verification/data collection.


We need to have your item-wise financial offer as per attached Bill of Quantity. The quotation of all items has to be submitted to us, which will be inclusive of material cost, wastage, cost for labor, carrying cost, income tax & VAT etc.

The financial offer for the Captioned Work is to be submitted to Facility Management Division, Prime Bank Limited, Head Office, 29 Rajuk Avenue (2nd floor), Dhaka-1000 by 3.00 p.m on 29.01.2019 and may be opened at 3.30 pm on the same day in presence of bidders (if any). For further details, you may contact Facility Management Division, Head Office, 29 Rajuk Avenue (2nd floor), Dhaka-1000 during office hours.


Please note that awarding of the job shall be subjected to the approval of the competent authority as per rules and procedure of our Bank without any binding on our part.

The Bank reserves the right to reject any or all of the proposals without assigning any reason whatsoever, or waive any irregularity in the proposal and the Bank will not be bound to accept either the lowest financial proposal or any other proposal.

Thanking you.



Md. Imran Shekh
Officer (Civil Engr.)



Md. Mir Murad Ali
Senior Assistant Vice President

**BOQ for Shifting Internal Audit Department from 2nd, 6th & 7th Floor of
Alhaj Tower to 2nd Floor of Facilities Tower**

SL. NO.	ITEMS	SPECIFICATION	WORK DETAIL	QUANTITY	UNIT	RATE	AMOUNT (TK.)
A	SHIFTING WORK						
1	Fixed Glass		Dismantling, Shifting, Installing with Necessary Accessories	744	sft		
2	Sliding Glass			168	sft		
3	Single Swing Glass Door			2	nos		
4	Fabric Partition			1,897	sft		
5	Table	6'x3'		1	nos		
6		5'x2.5'		4	nos		
7		4.5'x2'		51	nos		
8	Side Table	3'x1.5'		5	nos		
9	Chairs	75 nos		Shifting	1	LS	
10	Full Height Cabinet	5'4"x8'	Dismantling, Shifting, Installing with Necessary Accessories	1	nos		
11		3'10"x8'		1	nos		
12		2'7"x8'		1	nos		
13		7'11"x8'		1	nos		
14	Low Height Cabinet	71"x3.5'		1	nos		
15		60"x3.5'		1	nos		
16		56"x3.5'		1	nos		
17		48"x3.5'		13	nos		
B	CIVIL WORK						
1	Tiles Dismantling			200	sft		
2	Tiles Fitting	RAK 24"x24"		200	sft		
3	Painting			4,856	sft		
4	Vertical Blinds Cleaning			1,220	sft		
C	SANITARY WORK						
1	Sink Dismantling			1	nos		
2	Counter Dismantling	Including Rubbish Removing		1	LS		
3	Standing Urinal			1	nos		
4	Plumbing Work	With Necessary Pipe Fittings		1	nos		
D	NETWORKING WORK						
1	Cat 6 UTP Cable (3M-USA)			12	coil		
2	Cat6 Patch Panel with modular (3M-USA)			5	pcs		
3	Wire Manager (3M-USA)			5	pcs		
4	Cat6 Single Face Plate with Modular (3M-USA)			24	pcs		
5	Cat6 Dual Face Plate with Modular (3M-USA)			34	pcs		
6	M.K. Box			58	pcs		
7	¾ PVC Pipe Fittings			200	pcs		
8	Factory built Cat6 Mounting Cord 1m (3M-USA)			50	pcs		
9	Factory built Cat6 Patch Cord 3m (3M-USA)			30	pcs		
10	Installation & Commissioning Charge			92	pcs		
11	CAD Design			1	pcs		
12	Network Switch- 24 Port			1	pcs		
E	ELECTICAL						
1	Pipe Work						
a	CONCEALED/ EXPOSED CONDUIT						
	Supply and laying of following water grade PVC pipe (RFL Brand) and flexible pipe(RFL). exposed on ceiling/ hanger/under floor/partition board as per routing for wiring of power socket outlet, lighting and telephone socket. The rate shall be inclusive the cost of accessories such as bends,tee,socket, circular box, pull wire, wooden screw,groove cutting etc. all complete as per full satisfaction of Engineer in charge.						
i)	PVC Pipe, 1" diaX10ft,Brand:RFL			600	rft		
ii)	PVC Pipe, 3/4" diaX10ft,Brand:RFL			600	rft		
iii)	Flexible Pipe,3/4 " dia,Brand:RFL			400	rft		



SL. NO.	ITEMS	SPECIFICATION	WORK DETAIL	QUANTITY	UNIT		
iv)	Flexible Pipe,1 " dia,Brand:RFL			200	rft		
v)	Plastic channel(white),3/4"X10ft			200	pcs		
2	Cable Work						
b	Cables Supply & installation and connection with lighting fixture, power socket out let, Telephone socket and Circuit Breaker including all accessories of the following cables,all complete as per full satisfaction of Engineer in charge.						
i)	Cable 1X3.0rm,7-w,BYA,BRB/Paradise(For power socket connection)			8	coil		
ii)	Cable 1X1.3 rm,3-w, BYA,BRB/Paradise(For light point and power points internal wiring)			3	coil		
iii)	Telephone cable, 2- pair,BRB/Super sign			8	coil		
iv)	Telephone cable, 25- pair,BRB/Super sign			140	rft		
v)	Telephone connector(koron),10 terminal			4	sets		
3	Earth Continuty conductor						
c	Supply,installation and connection with power sockets and earth terminal of MDB/SDB/ESDB. metallic parts of following sizes etc. all complete as per full satisfaction of Engineer in charge.						
i)	1x2 rm,3-w,BYA,BRB/Paradise Green color(with power points)			2	Coil		
4	CIRCUIT BREAKER COONNECTION(FOR POWER SOCKETS)						
d	Supply, installation and connection Circuit Breaker inside existing MDB/SDB/ESDB Box, all complete as per direction and full satisfaction of Engineer in charge.						
i)	MCB-20A,SP , Brand:Legrand,Made: India			6			
5	Dismantting and re-install of following socket out lets from existing stock :						
i)	3-pin,13A,universal(combined) power socket, Type:Legrand Synergy Brand:Energypac			65	Nos		
ii)	3-pin(flat),13A,power socket, MK type			64	Nos		
iii)	T&T socket out let, MK type			58	Nos		
vi)	Internet socket outlet			62	Nos		
6	Light Fittings						
e	LED Tube Light,1X20W, 4ft(Industrial type) set Supply, fixing and connection as locally available LED tube light set with tube,20watt, Brand: Energypac, (2-years warranty) of approved color & size. with other necessary accessories etc. all complete up to testing & commissioning as per fullsatisfaction of Engineer in charge.			53	sets		
Total TK.							

In Word:

