

Facility Management Division

Prime/HO/FMD/RFQ/2021/637

November 24, 2021

Subject : RFQ For Repair and Renovation Works (Exterior) Of Banani Branch.

We would like to inform you that we are inviting RFQ for Repair and Renovation Works (Exterior) Of Banani Branch, Dhaka.

You may participate in the RFQ procedure by submitting Financial Proposal in sealed envelope for the captioned work. If you are interested, you may visit to above mentioned places for verification/data collection.

Eligibility and other conditions:

1. Interested bidders may participate the RFQ as well as should have documentary evidence of the followings:
 - i) Should have minimum experience of 03 (Three) years in Repair and Renovation work of any Bank's Branch or Head Office.
 - ii) Must have experience of executing work of Tk.15.00 Lac or above in a single tender.
 - iii) Should have valid Registration, ownership document, VAT & TIN certificate, up-to-date Trade License and Bank Solvency Certificate.
2. As per attached Bill of Quantity, the quotation of all items has to be submitted to us, which will be inclusive of material cost, wastage, cost for labor, carrying cost, income Tax & VAT etc.
3. The interested bidders may attend a pre-bid meeting at the office of the undersigned **at 11:00 am on 28.11.2021**
4. The financial offer for the Captioned Work is to be submitted in the Tender Box kept at Facility Management Division, Prime Bank Limited, Head Office, Facilities Tower (6th Floor), Kha-199/2, Maddhya Badda, Pragati Sarani, Dhaka-1212 **by 12:00 p.m on 30.11.2021 and may be opened at 02.30 pm on the same day.** To avoid social gathering for the present pandemic situation, no bidders will be invited during the opening. However, participants list and financial status will be shared among the bidders through email.
5. Submission of RFQ after the specified time shall not be acceptable under any circumstances.

Please note that awarding of the job shall be subjected to the approval of the competent authority as per rules and procedure of our Bank without any binding on our part.

The Bank reserves the right to reject any or all of the proposals without assigning any reason whatsoever, or waive any irregularity in the proposal and the Bank will not be bound to accept either the lowest financial proposal or any other proposal.

For details information, you may call Md. Delwar Hoosain Saigy # 01701204025.

Thanking you.



Kazi Sohel Masud
AVP, Procurement
Cell # 01730 028367

BOQ: REPAIR AND RENOVATION WORKS (EXTERIOR) OF BANANI BRANCH.					
SI.NO	ITEMS	UNIT	QUANTITY	RATE TK	AMOUNT TK
1	Dismantling work :Dismantling of 5" ,10" wall, tiles Marble etc. at all the level and any shape included all necessary need tools and staging equipment of scaffolding/ bamboo staging etc and labor. Also removal of debris, disposing the same way form the site location . including loading and unloading disposal and cleaning the site.	sft	1500		
2	Rusting tiles cleaning & repointing: Wash and cleaning the Rustic tile and repointing with necessary materials of tiles cleaner. Surface cleaning and making the dust-free and usage water proof Khadims tiles pointing or equivalent product. included all necessary need tools and staging equipment of scaffolding/ bamboo staging etc.	sft	1800		
3	Brick work: Brick work with 1st class brick in cement mortar (1:4) in super structure in/c racking out joints, filling the interstices with mortar, curing at least for 7 days etc. all complete as per direction and full satisfaction of the Architect/Engineer in charge.	sft	190		
4	PLASTIC PAINT (Berger/Asian or Equivalent) Painting work in 3 coats of plastic paint of approved colour and quality over a coat of primer, sealer including cleaning the surface, rubbibg by pumice stone, sand papering, synthetic putty and necessary scafolding for all floors etc included all necessary need tools and staging equipment of scaffolding/ bamboo staging etc.. all complete as per design, direction and full satisfaction of the Architect / Engineer in charge. (Sample to be approved before coating)	sft	1850		
5	PLASTER WORK Minimum 1/2" thick plaster with cement mortar (1:4) on walls both inter & outer surfaces. R.C.C surfaces before rough chipping of surfaces, finishing corners and edges and curing at least for 10 days etc.included all necessary need tools and staging equipment of scaffolding/ bamboo staging etc. all complete as per directionand full satisfaction of the Architect / Engineers in Charge.	sft	1400		



SI.NO	ITEMS	UNIT	QUANTITY	RATE TK	AMOUNT TK
6	Weather Coat Paint: Painting work in 3 coats of Weather coat paint of approved colour and quality over a coat of primer, sealer including cleaning the surface, rubbing by pumice stone, sand papering, synthetic putty and necessary scaffolding for all floors etc. all complete as per design, direction and full satisfaction of the Architect / Engineer in charge. (Sample to be approved before coating)	sft	6070		
7	Trim Tree : Trim the all trees any height by labor with necessary equipment's and staging tools. Also removal of debris, disposing the same way form the site location . including loading and unloading disposal and cleaning the site.	Job LS	1		
8	ACP Work: .Supply, fitting & fixing of aluminium composite panel (ALCO PANEL/ALCOPLA/ Approved brand) of approved quality [4mm thickness,] clad with extra ordinary fine finish on standard and necessary aluminium box section framing etc. all complete as per design, direction and full satisfaction of the Architect /Engineer in charge.	sft	210		
9	Supply fitting fixingof Rustic Tiles Work 24"x12"	sft	128		
10	SS post and SS steel Board : Supply fitting fixing 3"- 4" Stainless Steel post		120		
11	ENAMEL PAINT (Berger/Asian or Equivalent) Painting work in 3 coats of enamel paint of approved colour and quality over a coat of primer seal including cleaning the surface, sand papering, putty and necessary scaffolding for all floors etc. all complete as per design, direction and full satisfaction of the Architect / Engineer in charge.(Sample is to be approved before coating)	sft	380		
				TOTAL	

