

**Facility Management Division**

Prime/HO/FMD/2016/GEN/ 2 9 8 |

February 02, 2016

Sub: Request for Quotation (RFQ) for supply, installation, testing & commissioning of 3-Phase Prime Power 20kVA/Standby Power 22kVA Diesel Generator with ATS and Canopy on turn-key basis for Rangpur branch, Rangpur.

Dear Sir,

Please know that Prime Bank Limited intends to purchase one unit of generator as mentioned in captioned subject. For this purpose, we are inviting you to submit financial offer along with technical specification of your product in your letterhead pad using following format:

Table-A: Bill of Quantity (BOQ)

SL	Particulars	Qty	Unit	Unit Price, Tk.	Total Price, Tk.
1	3- Phase Prime Power 20KVA/Standby Power 22KVA Diesel Generator Brand: Model: Country of assembly: Country of shipment:	1	No		
2	Skid mounted Foreign standard Sound Attenuated Canopy Local assemble (Sound-level: 80db@1m)	1	No		
3	Auto Transfer Switch (ATS) (Local assemble) Rating of magnetic contactor:	1	No		
(i) Sub-total (Genset)					
(ii) Required consumable items for periodic servicing for 2 years (Total 6 times)					
Total (i+ii)					

Table-B: Unit rate of Installation Materials

SL	Particulars	Unit	Unit Price, Tk.
1	Power cable, 1x10mm NYY (BRB)	RFT	
2	Control cable (BRB) (as required)	RFT	
3	Earthing cable, 1x10mm BYA	RFT	
4	Flexible pipe, 2.5" dia	RFT	
5	Supply, fitting of Silencer exhaust	RFT	
6	Supply, fitting of Ducting	SFT	
7	Diesel for commissioning	Ltr	
8	Other installation materials: Cable lugs, nut, bolt, tape etc (total price)	1 job	

**Terms & Conditions:**
**1. Delivery & Installation:**

- A. From ready-stock (1 week).
- B. The supplier will deliver & install the products to the Bank's selected location. No additional cost will be paid by the bank for transportation.
- C. In case of supply of interior quality/defective goods; any change request by Prime Bank must be entertained.