



Facility Management Division

Prime/HO/FMD/2019/ ৪৭৭

June 23, 2019

Sub : RFQ for Interior, Exterior Decoration and Furniture works of new premises for Thakurgaon SME/Agri Branch which will be shifted/relocated to 1st floor, "Doctor Aziz Complex", Bangabandhu Road, Thakurgaon.

Dear Sir,

Reference may please be made on the above mentioned subject.

We would like to inform you that we are inviting tender for Interior, Exterior Decoration and Furniture works of new premises for Thakurgaon SME/Agri Branch which will be shifted/relocated to 1st floor, "Doctor Aziz Complex", Bangabandhu Road, Thakurgaon.

You may participate in the tender procedure by submitting Financial Proposal in sealed envelope for the captioned work. If you are interested, you may visit to above mentioned places for verification/data collection.

Eligibility and other conditions:

1. Interested bidders may collect tender document for the said work on submission of a request letter addressing the undersigned as well as documentary evidence of the followings:
 - i) Should have minimum experience of 03 (Three) years in Interior Decoration and Furniture work of any Bank's Branch or Head Office.
 - ii) Must have experience of executing work of Tk.25.00 Lac or above in a single tender.
 - iii) Should have valid Registration, ownership document, VAT & TIN certificate, up-to-date Trade License and Bank Solvency Certificate.
2. As per attached Bill of Quantity, the quotation of all items has to be submitted to us, which will be inclusive of material cost, wastage, cost for labor, carrying cost, income tax & VAT etc.
3. The interested bidders shall have to attend a pre-bid meeting at the office of the undersigned **at 3:00 pm on 27.06.2019.**
4. The financial offer along with design/drawing for the Captioned Work is to be submitted to Facility Management Division, Prime Bank Limited, Head Office, 29, Rajuk Avenue (2nd floor), Dhaka-1000 **by 3.00 p.m on 02.07.2019 and may be opened at 3.30 pm on the same day in presence of bidders (if any).**
5. Submission of tender after the specified time shall not be acceptable under any circumstances.

Cont'd page-02

Please note that awarding of the job shall be subjected to the approval of the competent authority as per rules and procedure of our Bank without any binding on our part.

The Bank reserves the right to reject any or all of the proposals without assigning any reason whatsoever, or waive any irregularity in the proposal and the Bank will not be bound to accept either the lowest financial proposal or any other proposal.

Thanking you.



Md. Delwar Hoosain Saidy
Officer (Civil Engr.)



Md. Mir Murad Ali
Senior Assistant Vice President

**QUOTATION FOR INTERIOR, EXTERIOR DECORATION & FURNITURE
WORKS OF NEW PREMISES FOR SHIFTING/RELOCATION OF
THAKURGAON SME/AGRI. BRANCH, THAKURGAON.**

ABSTRACT

A.	Civil Work	Tk.	
B.	Paint Work	Tk.	
C.	Granite/Marble/Tiles Work	Tk.	
D.	Partition & Paneling Work	Tk.	
E.	Ceiling Work	Tk.	
F.	Door Work	Tk.	
G.	Electrical Work	Tk.	
H.	Miscellaneous Work	Tk.	
I.	Furniture Work	Tk.	
J.	Shifting Furniture	Tk.	
	TOTAL (BRANCH)	Tk.	
K.	ATM Booth Work	Tk.	
	GRAND - TOTAL	Tk.	

In word :



Quotation for Interior, Exterior Decoration and Furniture Works of new premises for Shifting/relocation of Thakurgaon SME/Agri Branch, Thakurgaon.

Sl.	Description	Unit	Quantity	Rate (BDT)	Amount (BDT)
A. Civil Work					
1	TELLER COUNTER Teller counter made of 5" brick walls with plaster finish as supports, on top of brick wall 3/4" thick Black Galaxy Granite slab of 20" wide laid over 3" thick R.C.C. slab (1:2:4).The granite top will drop by 2'-0" at front side of the counter over 2.5" thick R.C.C. slab (1:2:4) which will hide a tube light rail and and working top of the counter should be made of 1.5" thick beech color laminated baord including electrical power point provision and glass shield made 10 mm glass etc. all complete as per approved design, direction and full satisfaction of the Engineer in charge.(Same as IK Tower , Gulshan.)	rft	13.00		
2	SERVICE COUNTER / GENRAL BANKING COUNTER Supply, making, fitting & fixing of service counter and general banking counter made of 5" brick wall with plaster finish on top of brick wall 3/4" thick Black Galaxy Granite slab of 2'-6" wide laid over 3" thick R.C.C. slab (1:2:4).The granite top will drop by 6" at front side of the counter over 2.5" thick R.C.C. slab (1:2:4) and 1/2" thick Tan Brown Granite at the lower portion of the front side of the counter etc. all complete as per approved design and as per direction and full satisfaction of the Engineer in charge. (Same as IK Tower , Gulshan.)	rft	9.00		
3	KITCHEN COUNTER Supply, fitting & fixing of 18 mm thick White Carara Marble on 2.5" thick R.C.C. slab (1:2:4) with 19 mm thick cement mortar (1:2) including necessary 5" brick wall support (Plaster finish), laying, cutting, grinding and polishing the stone, proper pointing etc. all complete as per direction and full satisfaction of the Engineer in charge.	rft	4.00		
4	TOILET BASIN COUNTER	rft	3.00		
5	RCC WORK (For Vault casting) Reinforcement cement concrete works (1:2:4) having minimum crushing strength 4000 psi (cylinder) at 28 days with cement, best quality coarse sand (25% quantity of the best local sand (F.M.-1.5) and 75% quantity of Sylhet sand or coarse sand of equivalent (F.M.-2.5) 3/4" down grade stone chips including braking chips and screening, centering, shuttering, Supplying Polythene sheet (1 kg covering 6.5 sq. meter) for making shuttering leak proof, placing of rod in position, mixing the aggregates including the use of quick setting retarded with mixer machine hand mixing casting in forms, compacting by vibrator machine & curing at least for 7 days (excluding the cost of reinforcement, all fabrication and all other related work) etc. all complete (Including scaffolding here requires) as per design, direction, and satisfaction of the Architect/Engineer.	cft	305.00		
6	NET CEMENT FINISH	sft	100.00		
7	ROLLING SHUTTER Supply, fitting & fixing steel rolling shutter made of strips imported G.P. sheet of approved thickness and quality including locking arrangement and paint finish etc. all complete as per direction and full satisfaction of the Engineer in charge. (Brand: Yunusco Ltd. or equivalent.)	sft	60.00		
8	BRICK WALL (5")	sft	90.00		
9	PLASTER	sft	1,000.00		
10	COLLAPSIBLE GATE (MS)	sft	64.00		
Sub-Total Tk.					

